



20th October 2022

REFERENCE NUMBER: SPD3/2022/065

CONSTRUCTION, FINISHING WORKS AND COMMISSIONING OF AN E-TICKETING PROJECT AT CIRKEWWA AND MGARR PASSENGER FERRY TERMINALS

Clarification No. 2

Clarifications

Question 1: Bill 2- Cable Mgmt requires galvanised steel cable trunking 75 x 75mm, however the specifications only refer to galvanised steel cable trays. Is this cable trunking to be used instead? If so, is it to be installed vertically or horizontally?

Answer 1: Bidders are requested to use cable trunking for LV cables as requested in the bill of quantities and as shown in the tender documents. Trunking shall be of the galvanised sheet steel type and shall be installed horizontally above soffit with vertical down drops wherever necessary with particular attention to the Cirkewwa ticket booths and new kiosk.

All other tender documents, conditions and requirements, which are not superseded by this Clarification, remain in place.

*Sectoral Procurement Unit 3
Sectoral Procurement Directorate*